



USN

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

NMAM INSTITUTE OF TECHNOLOGY, NITTE
Off-Campus Centre of Nitte (Deemed to be University)
Seventh Semester B.Tech (CBCS) Degree Examinations

December 2025

CV2008-1 – QUANTITY SURVEYING AND ESTIMATION

(For CIV)

Duration: 3 Hours

Max. Marks: 100

Note:

Part – A: Multiple Choice Questions: Answer all **Twenty** questions in the **OMR Sheet** provided. Each question carries equal marks.

Part – B: Descriptive Answer Questions: Answer the two compulsory questions from **Unit-I**, any two full questions from **Unit-II**, and one full question from **Unit-III**.

PART - A: MULTIPLE CHOICE QUESTIONS**20 Marks**

1. The process of calculating quantities and costs of materials required for a construction project is called
 - A) Valuation
 - B) Estimation
 - C) Depreciation
 - D) Analysis
2. The rate of materials and labour is taken from
 - A) Bill of Quantities
 - B) Schedule of Rates (SR)
 - C) Drawing
 - D) Measurement book
3. The total cost of a building includes
 - A) Material cost only
 - B) Labour cost only
 - C) Material + Labour + Overheads
 - D) Contractor's profit only
4. In long wall-short wall method, the length of long wall is measured as:
 - A) Center to center + half breadth
 - B) Inner to inner
 - C) Outer to outer
 - D) Center to center- half breadth
5. The estimate which is prepared for administrative approval is called:
 - A) Preliminary estimate
 - B) Detailed estimate
 - C) Revised estimate
 - D) Supplementary estimate
6. The most accurate type of estimate is:
 - A) Preliminary
 - B) Detailed
 - C) Rough cost
 - D) Abstract
7. The unit of measurement for R.C.C work is
 - A) Square meter
 - B) Running meter
 - C) Cubic meter
 - D) Lump sum
8. The main objective of specification is to
 - A) Increase the project cost
 - B) Reduce labour
 - C) Describe the nature and quality of work
 - D) Fix rate of items
9. The essential requirement of a good specification is:
 - A) Clarity
 - B) Lengthy description
 - C) Ambiguity
 - D) Complicated language
10. General specification gives:
 - A) Detailed description of each item
 - B) Brief description of class and quality of work
 - C) Contractor's experience
 - D) Rate of materials



11. In rate analysis, hire charges of tools & plants are considered as
 - A) Material cost
 - B) Overheads
 - C) Direct labour
 - D) Wastage
12. The specification of cement mortar 1:6 means:
 - A) 1 part cement and 6 parts sand
 - B) 1 part water and 6 parts cement
 - C) 1 part sand and 6 parts cement
 - D) 1 part lime and 6 parts sand
13. Rate analysis means:
 - A) Working out the cost of materials only
 - B) Checking profits
 - C) Determining the per unit cost of an item
 - D) Determining total project cost
14. The mix ratio for M20 grade concrete is:
 - A) 1:1:2
 - B) 1:1.5:1
 - C) 1:1.5:3
 - D) 1:1:3
15. The process of inviting contractors to submit bids for a project is called:
 - A) Tendering
 - B) Contracting
 - C) Bidding evaluation
 - D) Award of work
16. The main purpose of prequalification in tendering is to:
 - A) Reject all bidders
 - B) Select financially and technically capable contractors
 - C) Reduce tender cost
 - D) Award contract early
17. Time extension in contract is granted due to
 - A) Contractor's negligence
 - B) Natural calamities
 - C) Lack of labour
 - D) Profit issues
18. Retention money in contracts is meant for
 - A) Profit of contractor
 - B) Insurance cover
 - C) Ensuring defect liability period compliance
 - D) Extra payment
19. Arbitration in contract disputes means
 - A) Approval of tender
 - B) Blacklisting contractor
 - C) Termination of contract
 - D) Negotiation by third party
20. Administrative approval refers to:
 - A) Approval of drawing
 - B) Approval of contractor
 - C) Approval of cost estimate by competent authority
 - D) Approval of tender

PART - B: DESCRIPTIVE ANSWER QUESTIONS

Unit – I		Marks	BT*	CO*	PO*
1.	Develop the detailed and abstract estimate for the plan shown in the figure 1 by using center line method and estimate the quantities for i. P.C.C bed 1:3:6 for foundation. ii. First class brick work in 1:4 Cement mortar for super structure excluding Parapet wall.	16	L*3	1	1,2
2.	Develop the detailed and abstract estimate for the plan shown in the figure 1 by using long wall short wall method and estimate the quantities for i. Earthwork excavation for foundation in ordinary soil. ii. S.S.M in C.M 1:4 for foundation and plinth.	16	L3	2	1,2
Unit – II					
3.	a) Explain the detailed specification for granite tile flooring, including materials, surface preparation, laying procedure, jointing, and finishing.	08	L2	3	1,2

b)	Solve the rate analysis of R.C.C. work (1:2:4) for a roof slab with 1.5% steel, assuming suitable rates for materials and labor.	08	L3	4	1,2
4. a)	Explain the detailed specification for second-class brickwork in cement mortar 1:4, including materials, mortar preparation, brick laying procedure, curing, and workmanship standards.	08	L2	3	1,2
b)	Solve the rate analysis of second-class brickwork in superstructure using 20 × 10 × 10 cm bricks with 1:4 cement mortar, assuming suitable rates for materials and labor.	08	L3	4	1,2
5. a)	Explain the detailed specification for R.C.C.(1:1.5:3) work, including materials, mix design, reinforcement detailing, shuttering, placing, compaction, curing, and quality control measures.	08	L2	3	1,2
b)	Solve the rate analysis of plain cement concrete (1:4:8) in foundation, assuming suitable rates for materials and labor.	08	L3	4	2,3
Unit – III					
6. a)	What is tender? Explain its Necessity in civil engineering work.	08	L2	5	1,8
b)	Explain in detail Technical sanction	08	L2	5	1,8
7.	Explain the following contract management terminology				
a)	Suspension of work	08	L2	5	1,8
b)	Breach of contract	08	L2	5	1,8

BT* Bloom's Taxonomy, L* Level; CO* Course Outcome; PO* Program Outcome.